

## **Project Number 50176**

# Construction of Green Stormwater Infrastructure (GSI)

Anticipated Start Date: TBD Anticipated Completion Date: TBD



#### Areas impacted by construction:

- Wolf Street from S. Lambert St. to S. Garnet St.
- Wolf St from 20th St. to 19th St.
- S. 19th St from W. Ritner St. to Durfor St.
- S. 18th St from W. Ritner St. to Wolf St.
- W. Ritner Street from S. 21st St. to S. 20th St.
- S. 20th Street from W. Ritner St. to Durfor St.
- W. Porter Street from S. 21st St. to S. Lambert St.
- W. Porter Street from S. 20th St. to S. Garnet St.

## Why are we doing this project?

State and federal regulations require Philadelphia to reduce the pollution entering our rivers when excess stormwater causes sewer overflows. **Green City, Clean Waters** is a program designed to meet those regulations and invest in neighborhoods across the city by creating stormwater infrastructure that incorporates green space.

In addition to water quality benefits, green tools used by **Green City, Clean Waters** provide a number of community benefits. New green spaces have been found to **improve the value of homes** and **encourage outdoor recreation** while **reducing stress**, **noise**, **air pollution** and **litter** in neighborhoods.

## What is green stormwater infrastructure?

Green stormwater infrastructure (GSI) uses materials such as plants, soil, stone and special pavement to slow, filter and soak up water during storms. This project includes the following types of green stormwater infrastructure:

**Stormwater Tree Trench** - A stormwater tree trench looks like a series of traditional street trees, but underground the trees are connected by a concrete structure designed to store and filter water. During construction, a trench is created along the sidewalk and lined with special fabric, then filled with stone and topped with soil and trees.

**Stormwater Bumpout** - A stormwater bumpout is a landscaped extension of the curb. Underneath the bumpout is a large concrete storage system filled with gravel or stone and topped off with soil. Grasses, perennials and shrubs are planted on top of the storage system.

**Underground Storage** - Underground or subsurface storage refers to spaces that store stormwater underground. Typically, a rectangular bed is cut in the street or sidewalk. The bed is lined with special fabric and then filled with stone or gravel and sometimes plastic storage pipes.



Plants filter water and enhance streetscape. Water filters through soil.



At Right: Graphic rendering of a completed bumpout similar to the one to be constructed Wolf Street near S. 20th Street.

#### Stone and other materials prov additional stormwater storage.

# Frequently Asked Questions (FAQs)

flows from street

into bumpout.

With all construction there is a level of inconvenience. Philadelphia Water is working to minimize construction impacts. Please refer to our Frequently Asked Questions for more information:

#### Q: Will I lose water service during construction?

- A: Water service will not be affected during construction.
- Q: Will other utilities be interrupted during construction?
- A: No disruption of utilities is anticipated during this construction period.

#### Q: What are the hours of construction?

- A: Typical construction hours are from 7:00 a.m. to 4:00 p.m. but can vary seasonally.
- Q: How will construction impact traffic, sidewalk access and parking?
- A: Street parking during hours of construction will be restricted. Temporary "No Parking" signs will be installed as needed for safety and construction. Signs will be installed before the start of work indicating the dates and hours that the areas will be closed.
  Vehicular traffic, pedestrian access, trash collection and deliveries will be maintained. Any cars left on streets where work is scheduled to take place will be towed to a nearby public street. Project personnel will be available to direct you to your car.

#### Q: How dusty will my street be during construction?

A: All construction work is subject to dirt and dust, but we try to keep it to a minimum. At the end of each work day, the contractor will be responsible for keeping the site clean.

#### **Q: Will trees be protected during construction?**

A: A tree specialist will assess all trees in the project area prior to construction to identify measures to protect the trees.

#### Q: Will SEPTA service in the area be impacted?

A: Yes. SEPTA Bus Route 17 along S. 19<sup>th</sup> Street and S.
 20<sup>th</sup> Street may be impacted. Visit SEPTA.org for more information.

# Q: Once the project is built, who will maintain the new plants and trees?

A: Philadelphia Water is responsible for maintaining all of our infrastructure, including green stormwater infrastructure. We visit sites about once a month to perform routine maintenance.