

Table E-6: Standard Sequence of Construction Notes

#	Note
1	At least seven (7) days prior to any earth disturbance, the Inspections Coordinator of PWD (Office: 215-685-6387) must be called to schedule a preconstruction meeting.
2	At least three (3) days prior to (<i>applicant to name each SMP</i>) installation, the Inspections Coordinator of PWD (Office: 215-685-6387) must be called to schedule an inspection (<i>for each SMP</i>).
3	All stone that makes up the (<i>applicant to name each infiltration SMP</i>) must remain free of sediment. If sediment enters the stone, the contractor may be required to remove the sediment and replace it with clean-washed stone.
4	Upon completion of all earth disturbance activities and permanent stabilization of all disturbed areas, the owner and/or operator shall contact Inspections Coordinator of PWD (Office: 215-685-6387) for a final inspection prior to removal/conversion of the E&S BMPs.
5	As soon as slopes, channels, ditches, and other disturbed areas reach final grade, they must be stabilized. Cessation of activity for four (4) days or longer requires temporary stabilization.
6	The NPDES Notice of Termination (N.O.T.) must be submitted to PA DEP upon completion of construction (<i>when applicable</i>).
7	Water pumped from work areas should be treated for sediment removal prior to discharging to a “surface water” (<i>when applicable</i>).